

CARR-1421

3114 Kump Station Road
Taneytown (vicinity)

Summary:

The house at 3114 Kump Station Road is a central gable I-house, a type that became rather popular in Carroll County beginning in the 1880's in towns, and was built on farms mostly in the late 1890's and early twentieth century. The front door of this house is identical to the front door of the Sallie and Samuel Sterner house (CARR-1387), which was built c. 1898. The 1877 map does not show a building here, but suggests that the lot was part of a farm owned by Mrs. Myers. The house was standing by 1917, and was owned then by Russell Myers. Presumably, he inherited or purchased the farm from his mother and built a new house at that time, c. 189-1905, although further research is needed to verify this. The house probably had a front porch, originally. The summer kitchen most likely dates from the same time as the house.

**Maryland Historical Trust
State Historic Sites Inventory Form**

**MARYLAND INVENTORY OF
HISTORIC PROPERTIES**

Survey No. CARR-1421

Magi No.

DOE yes no

1. Name (indicate preferred name)

historic

and/or common

2. Location

street & number 3114 Kump Station Road

 not for publication

city, town Taneytown

 X vicinity of

congressional district

state Maryland

county Carroll

3. Classification

Category

 district

 X building(s)

 structure

 site

 object

Ownership

 public

 X private

 both

Public Acquisition

 in process

 being considered

 X not applicable

Status

 X occupied

 unoccupied

 work in progress

Accessible

 yes: restricted

 yes: unrestricted

 X no

Present Use

 agriculture

 commercial

 educational

 entertainment

 government

 industrial

 military

 museum

 park

 X private residence

 religious

 scientific

 transportation

 other:

4. Owner of Property (give names and mailing addresses of all owners)

name James and Mary May

street & number 3114 Kump Station Road

telephone no.: 346-7201

city, town Taneytown

state and zip code Maryland 21787

5. Location of Legal Description

courthouse, registry of deeds, etc. Courthouse Annex

liber 195

street & number 55 North Court Street

folio 460

city, town Westminster

state Maryland

6. Representation in Existing Historical Surveys

title

date

 federal state county local

pository for survey records

city, town

state

7. Description

Survey No. CARR-1421

Condition

☐ excellent
☐ good
☒ fair

☐ deteriorated
☐ ruins
☐ unexposed

Check one

☐ unaltered
☒ altered

Check one

☒ original site
☐ moved date of move _____

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

Contributing Resources: 2

The house at 3114 Kump Station Road is located on the north side of the road several hundred feet east of Stone Road, approximately 3½ miles northeast of Taneytown in northwest Carroll County, Maryland. The house faces southwest toward the road and is a 2½ story three-bay by two-bay central gable dormer structure with a rubble stone foundation, aluminum siding, and a gable roof with a northwest to southeast running ridge and asphalt shingles. The southwest elevation on the first story has a center entrance with a twelve-panel door. The panels are arranged with two tall panels on the bottom, a lying panel in the center, and nine panels at the top, the four corner panels being small and square and the center panel being large and roughly square. On each side of this center entrance is a 2/2 double hung sash. The second story has three 2/2 sash. The wall dormer has a lancet-shaped 1/1 sash. The northwest elevation has a new exterior brick chimney. The first story has two 2/2 sash, as does the second story. The gable end has two one-light sash. On the southeast elevation there is an interior brick chimney centered on the gable ridge. The first story has an enclosed porch set on stone piers. The second story has two 2/2 sash and the gable end has two one-light sash.

There is a summer kitchen approximately 30 feet southeast of the house. It has a rubble stone foundation, German siding with corner boards, and a gable roof of standing-seam metal with a northeast to southwest running ridge. It is a 1½ story structure that is two-bays by three bays. The northwest elevation has a beaded-edge vertical-board door with a six-light sash set into it in the west bay. The center bay has a 6/6 sash. there is a one-story shed-roof porch attached to the northwest elevation. The north bay of the porch is enclosed with German siding and this is probably an original treatment. The northwest elevation of this enclosure has a 6/6 sash while the southwest elevation has a six-panel door with the square panels set in the center. The southwest elevation of the summer kitchen has two 6/6 sash on the first story and one 6/6 sash centered in the gable end. There is an interior brick chimney on the northeast end. The southeast elevation has two 6/6 sash and appears to have a hurricane door leading to steps to the cellar.

8. Significance

Survey No. CARR-1421

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates

Builder/Architect

check: Applicable Criteria: ☐ A ☐ B ☐ C ☒ D
and/or

Applicable Exception: ☐ A ☐ B ☐ C ☐ D ☐ E ☐ F ☐ G

Level of Significance: ☐ national ☐ state ☒ local

Prepare both a summary paragraph of significance and a general statement of history and support.

Geographic Organization: Piedmont

Chronological/Development Period: Industrial/Urban Dominance A.D. 1870-1930

Historic Period Themes: Agriculture, Architecture

Resource Types: Small family farm, Rural vernacular

The house at 3114 Kump Station Road is a central gable I-house, a type that became rather popular in Carroll County beginning in the 1880's in towns, and was built on farms mostly in the late 1890's and early twentieth century. The front door of this house is identical to the front door of the Sallie and Samuel Sterner house (CARR-1387), which was built c. 1898. The 1877 map does not show a building here, but suggests that the lot was part of a farm owned by Mrs. Myers. The house was standing by 1917, and was owned then by Russell Myers. Presumably, he inherited or purchased the farm from his mother and built a new house at that time, c. 189-1905, although further research is needed to verify this. The house probably had a front porch, originally. The summer kitchen most likely dates from the same time as the house.

9. Major Bibliographical References

Survey No. CARR-1421

1877 & 1917 maps

10. Geographical Data

Acreage of nominated property 30 acres 7 8.5632 acres RP

Quadrangle name Littlestown

Quadrangle scale 1:24000

UTM References do NOT complete UTM references

A

Zone			Easting			Northing			

B

Zone			Easting			Northing			

C

--	--	--	--	--	--	--	--	--	--

D

--	--	--	--	--	--	--	--	--	--

E

--	--	--	--	--	--	--	--	--	--

F

--	--	--	--	--	--	--	--	--	--

G

--	--	--	--	--	--	--	--	--	--

H

--	--	--	--	--	--	--	--	--	--

Verbal boundary description and justification

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
-------	------	--------	------

state	code	county	code
-------	------	--------	------

11. Form Prepared By

name/title Kenneth M. Short, Historic Planner

organization Carroll County Planning Department

date December 8, 1994

street & number 225 North Center Street

telephone (410) 857-2145

city or town Westminster

state Maryland

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.


return to: Maryland Historical Trust
Shaw House
21 State Circle
Annapolis, Maryland 21401
(301) 269-2438

MARYLAND HISTORICAL TRUST
DHCP/DHCD
100 COMMUNITY PLACE
CROWNSVILLE, MD 21032-2023
514-7600

MYERS

DISTRICT N°3

Scale 14 inches to the Mile




CARR-1421

3114 Kump Station Road

Lake, Griffin & Stevenson Atlas, 1877

P E N N S Y L V A N I A



MYERS

ELECTION DISTRICT NO. 3.

CARROLL Co. Md.


EXPLANATION

TURNPIKE	=====
STATE ROAD	=====
HIGHWAY	=====
PRIVATE ROAD	-----
RAILROAD	=====
CHURCH	⛔
SCHOOL	⛎
MURKIN	⛎
CEMETERY	⛎
CITY OR VILLAGE BOUNDARY	-----
OWNERS NAME & ACREAGE	JNO SMITH 65.8
OWNER'S NAME	JOHN SMITH

CARR-1421

3114 Kump Station Road

Rand McNally Atlas, 1917



CARR-1421

3114 Kump Station Road

Assessments & Taxation Map 11, p. 294-1

COPYRIGHT-MAP DIVISION-1967
MD. DEPT. OF ASSESS. & TAX.

767

BASE MAP CONSTRUCTED
FROM 19 QUAD
PLANIMETRY REV TO
MAP DRAWN 16-5-70

770

5563 II NW
(TANEYTOWN)

4395

4394

4393

40'

4392


4391

4390

660 000 FEET
(MD.)

CARR-1421
3114 Kump Station Road

Littlestown quad





3114 Kump Station Rd.

Carroll County, Maryland

Photo: Kenneth M. Short

Date: Oct. 1994

Neg. Loc.: Maryland Historical Trust
house: Summer Kitchen - NW & SW elevs.

//